# ENGINEERING DEPARTMENT.

## GOVERNMENT OF MYSORE ELECTRICAL DEPARTMENT.

*Notification dated 15th September 1930.*

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M. on 13th October 1930, for constructing Office and Stores at Seringapatam.

1. The tenders will be opened in public at 2 P.M. on 13th October 1930. The time required to complete the work and monthly progress should be indicated, as these will be some of the chief factors in the award of tenders. The work should be completed within two months.

2. The plans, detailed estimates and conditions may be seen at the Chief Electrical Engineer's Office, Bangalore, on all working days during the office working hours.

3. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money, and be superscribed "Tenders for constructing Office and Stores at Seringapatam," in default of which, tenders will be rejected.

5. Final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the Notice Board in the Chief Electrical Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of the notification of the acceptance.

10. Any other conditions that the contractor may wish to state should also be included in his tender.

11. Water for construction should be got at the contractor's own expense.

12. Specifications for works are those recognised by the Mysore Public Works Department and Marryot's specifications.

13. The contractor should be bound by the conditions of the schedule of contract of the Electrical Department.

Statement showing the approximate quantities for constructing Office and Stores Buildings at..... ..... .....

| Serial No. | Items of work | Unit | Quantity | Rates in | |
|---|---|---|---|---|---|
| | | | | Figures | Words |
| | | | | Rs. | Rs. |
| 1 | Earthwork excavation for foundations including filling in basement. | C.yd. | 84 | | |
| 2(a) | Concrete stone jelly in mortar foundation ... | C.ft. | 310 | | |
| (b) | Stone in mortar foundation and basement including through stones at 6'-0" centre to centre in every course. | " | 762 | | |
| (c) | Burnt brick in clay superstructure ... | " | 1,327 | | |
| (d) | Burnt brick in mortar superstructure ... | " | 197 | | |
| (e) | Burnt stone slabs 4" thick roughly dressed and fixed in mortar. | S.ft. | 68 | | |
| (f) | Brick in mortar pillars 1:1/8 ft. square and 8'-0" high including stone capitals and bases and cement plastering ½" thick, etc., complete. | Each | 4 | | |
| (g) | Chunam plastering 2 coats .... ... | Sqr. | 28·80 | | |
| (h) | Chunam pointing ... ... ... | " | 1·80 | | |
| (i) | White and colour washing 2 coats .... | " | 30·40 | | |
| | ... 6" projection ... | R.ft. | 42 | | |

| Serial No. | Items of work | Unit | Quantity | Rates in Figures | Rates in Words |
|---|---|---|---|---|---|
| | | | | Rs. | Rs. |
| 3(a) | Flooring with Cuddapah slabs 1½″ thick on 3″ concrete and cement pointed. | Sqr. | 1·94 | | |
| (b) | Flooring with First Class Mangalore tiles on 3″ concrete and cement pointed. | ,, | 3·70 | | |
| 4(a) | Roofing with First Class Mangalore tiles on teak reepers 2″×1″. | ,, | 6·90 | | |
| (b) | Ridge tiles set in mortar and cement pointed | R.ft. | 27·5 | | |
| (c) | Madras terrace roofing 9″ thick plastering, etc., complete. | Sqr. | 2·15 | | |
| (d) | Brick in mortar cornice 9″ projection ... | R.ft. | 45 | | |
| e) | Parapet wall 1½′ high in mortar 9″ thick as per drawing. | ,, | 43 | | |
| (f) | Teakwood work with wood-oiling 2 coats ... | C.ft. | 39·53 | | |
| 5(a) | Teakwood panelled doors 1½″ thick shutters with fixtures, etc., complete. | S.ft. | 56·00 | | |
| (b) | Teakwood windows with glazed shutters 1″ thick and iron bars 5/8″ dia. with fixtures, etc., complete shutters to be of (4 leaves). | ,, | 87·50 | | |
| (c) | Teakwood rectangular ventilators with glazed shutters fixed complete. | ,, | 9·00 | | |
| (d) | Teakwood eave board plain 9″×¾″ fixed ... | R.ft. | 98 | | |
| (e) | Chacolate painting 2 coats ... ... ... | Sqr. | 4·50 | | |
| 6(a) | Steel work fixed complete with 2 coats of painting. | Cwt. | 11·40 | | |
| (b) | Fixing G. I. rain water down pipes 3″ diameter 22 B. W. G. fixed complete. | R.ft. | 44 | | |
| 7 | Fixing wire gauge shutters with iron fittings complete. | S.ft. | 63 | | |

C. M. CARIAPA,
*Chief Electrical Engineer.*

## KOLAR DIVISION.

*Dated 13th September* 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 4th October 1930, for Restoring Hale Somarasanhalli tank of Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Hale Somarasanhalli Tank, Kolar taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenderer must quote specific rates for all items both in words and figures.

10. The tenders stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

6 c